



---

### **Addendum Number 1**

**Bid:** Blackstrap Road Shoulder Box Cut  
Town of Falmouth – Public Works Department  
Falmouth, ME

**Date:** July 15, 2019

**From:** Justin Early, Town Engineer

#### **Questions, Clarifications, and Additional Information:**

1. The Lump Sum price shall include the cost to remove and replace the existing 18" CMP cross culvert with a new 18" HDPE culvert located at 363 Blackstrap Road. The length of the culvert is approximately 53 feet. See attached location map.

The price shall include the pipe material, excavation, installation, backfill and compaction to existing pavement grade. The pipe shall be backfilled according to the manufacture's recommendations and shall include 15" of MDOT Type "D" (703.06) gravel for the road base. The HMA paving will be installed by others under a separate project.

Please acknowledge receipt of this addendum by either emailing ([jeary@falmouthme.org](mailto:jeary@falmouthme.org)) a confirmation receipt, or writing in an acknowledgement on the bid form to be submitted.





**Blackstrap Road Shoulder Box Cut**  
Site Plan (Addendum #1)

