
BID SET No.

# TOWN OF FALMOUTH

**CONTRACT DRAWINGS FOR** 


# UNDERWOOD ROAD DRAINAGE IMPROVEMENTS

FALMOUTH, MAINE SEPTEMBER 2020



### **DRAWING INDEX**

<b>GENERAL</b>	
	COVER SHEET
CIVIL	
C-1	GENERAL NOTES, LEGEND AND ABBREVIATIONS
C-2	<b>EXISTING CONDITIONS AND DEMOLITION PLAN</b>
C-3	SITE LAYOUT PLAN
C-4	PROFILES
C-5	SECTIONS
C-6	DETAILS I
C-7	DETAILS II
C-8	EROSION CONTROL NOTES AND DETAILS
C-9	SUGGESTED CONSTRUCTION PHASING PLAN



**LOCATION PLAN** 



888.621.8156 | www.wright-pierce.com



FOR REVIEW
FOR BIDDING
9-23-2020

WP PROJECT No. 13042A

#### **GENERAL NOTES**

- 1. THE CONTRACTOR IS REFERRED TO SECTION 01050 OF THE SPECIFICATIONS REGARDING COORDINATION WITH OTHERS, INCLUDING RESPONSIBILITIES AND RELATED COSTS.
- 2. BELOW GRADE UTILITY INFORMATION IS BASED ON INFORMATION PROVIDED BY EACH UTILITY. LOCATION OF PUBLIC UTILITIES SHOWN IS ONLY APPROXIMATE AND MAY NOT BE COMPLETE. PRIVATE UNDERGROUND UTILITIES SUCH AS, BUT NOT LIMITED TO, SEWER LINES, WATER LINES AND BURIED ELECTRICAL SERVICE ENTRANCES ARE NOT SHOWN. THE CONTRACTOR SHALL ASCERTAIN THE LOCATION AND SIZE OF EXISTING UTILITIES IN THE FIELD WITH THE RESPECTIVE UTILITY COMPANY REPRESENTATIVE PRIOR TO COMMENCING WORK. REFER TO SPECIFICATION SECTION 01050. ADDITIONAL TEST PITS, BEYOND THOSE SHOWN, MAY BE REQUIRED. UTILITY CONTACTS ARE AS FOLLOWS:

ELECTRIC:

PORTLAND, MAINE 04101

TEL. (866) 984-2001

TEL. (800) 750-4000

**STORM DRAINS**:

MATER.

CENTRAL MAINE POWER CO. 162 CANCO ROAD SOUTH PORTLAND, MAINE 04103 TOWN OF FALMOUTH PUBLIC WORKS DEPT 101 WOODS ROAD FALMOUTH, MAINE 04105 PORTLAND WATER DISTRICT 225 DOUGLASS STREET PORTLAND, MAINE 04102 TEL. (207) 774-5961 X3052

**SANITARY SEWER:** 

EPHONE: <u>DIG SAFE</u>:

FAIRPOINT TEL. (888) 344-7233 45 FOREST AVENUE TOWN OF FALMOUTH WASTEWATER DEPT 96 CLEARWATER DRIVE

FALMOUTH, MAINE 04105 TEL. (207) 781-4462

CABLE TELEVISION:

SPECTRUM

364 MAINE MALL ROAD SPACE W 100

SOUTH PORTLAND, MAINE 04106

TEL. (888) 406-7063

SUMMIT NATURAL GAS

442 CIVIC CENTER DRIVE

AUGUSTA, MAINE 04330

TEL. (207) 621-8100

- 3. ALL EXISTING SEWER, STORM DRAIN, FORCE MAIN, WATER, AND GAS LINES ENCOUNTERED DURING CONSTRUCTION ARE TO REMAIN IN SERVICE. ANY EXISTING ACTIVE PIPES DAMAGED DURING CONSTRUCTION SHALL BE REPAIRED BY THE CONTRACTOR AT NO ADDITIONAL COST TO THE OWNER, EXCEPT WHEN IN DIRECT CONFLICT WITH THE NEW SEWER.
- 4. THE CONTRACTOR MAY ENCOUNTER ASBESTOS CEMENT PIPE DURING EXECUTION OF THE WORK. CONTRACTOR SHALL CONFORM TO ALL APPLICABLE PROVISIONS OF OSHA AND ALL OTHER FEDERAL, STATE AND LOCAL REGULATIONS WHEN HANDLING, REMOVING AND DISPOSING OF ASBESTOS CEMENT PIPES. A BID ITEM HAS BEEN INCLUDED IN THE BID FORM TO ESTABLISH A UNIT PRICE FOR THE REMOVAL AND DISPOSAL OF ASBESTOS CEMENT PIPE.
- 5. ALL STRUCTURES AND PIPELINES LOCATED ADJACENT TO THE TRENCH EXCAVATION SHALL BE PROTECTED AND FIRMLY SUPPORTED BY THE CONTRACTOR UNTIL THE TRENCH IS BACKFILLED. INJURY TO ANY SUCH STRUCTURES CAUSED BY, OR RESULTING FROM, THE CONTRACTOR'S OPERATIONS SHALL BE REPAIRED AT THE CONTRACTOR'S EXPENSE. ALL UTILITIES REQUIRING REPAIR, RELOCATION OR ADJUSTMENT AS A RESULT OF THE PROJECT SHALL BE COORDINATED THROUGH THE RESPECTIVE UTILITY.
- 6. IN THOSE INSTANCES WHERE POWER OR TELEPHONE POLE SUPPORT, RESETTING OR RELOCATING IS REQUIRED, THE CONTRACTOR SHALL PROVIDE A MINIMUM 48-HOUR NOTIFICATION TO THE UTILITY. NO ADDITIONAL PAYMENT WILL BE PROVIDED FOR TEMPORARY BRACING OF UTILITIES.
- 7. DO NOT SCALE DRAWINGS UNLESS OTHERWISE NOTED. WRITTEN DIMENSIONS AND STATIONING SHALL PREVAIL. TOPOGRAPHY BASED ON LIDAR DATA.
- 8. THE OWNER HAS OBTAINED THE PERMITS LISTED IN THE SUPPLEMENTARY OR SPECIAL CONDITIONS. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO BE FAMILIAR WITH THE APPLICABLE PROVISIONS OF EACH PERMIT AS THEY APPLY TO THE WORK PRIOR TO BIDDING AND ABIDE BY THOSE PROVISIONS DURING CONSTRUCTION. COPIES OF ALL OBTAINED PERMITS ARE AVAILABLE FOR REVIEW FROM THE TOWN OF FALMOUTH. ALL OTHER PERMITS ARE THE RESPONSIBILITY OF THE CONTRACTOR.
- 9. THE OWNER SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY RIGHTS OF WAY AND EASEMENTS. THE CONTRACTOR SHALL VERIFY THAT THE NECESSARY EASEMENTS HAVE BEEN SECURED BY THE OWNER. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO BE FAMILIAR WITH THE APPLICABLE PROVISIONS OF EACH EASEMENT AS THEY APPLY TO THE WORK PRIOR TO BIDDING AND ABIDE BY THOSE PROVISIONS DURING CONSTRUCTION. COPIES OF ALL RIGHTS-OF-WAY AND EASEMENTS ARE AVAILABLE FOR REVIEW FROM THE TOWN OF FALMOUTH.
- 10. CONTRACTOR SHALL MINIMIZE CLEARING OPERATIONS. CLEARING AND GRUBBING SHALL BE IN ACCORDANCE WITH SPECIFICATION SECTION 02110. CLEARING LIMITS SHALL BE AS INDICATED ON THE DRAWINGS, BUT AT ALL TIMES WITHIN EXISTING ROAD RIGHTS-OF-WAY AND EASEMENTS. ALL GRUBBINGS AND EXCESS EXCAVATED MATERIAL ARE THE PROPERTY OF THE CONTRACTOR AND WILL BE DISPOSED OF AT A SITE PROVIDED BY THE CONTRACTOR IN COMPLIANCE WITH ALL STATE AND LOCAL LAWS.
- 11. COMPACTION TESTS SHALL BE PERFORMED IN ACCORDANCE WITH SPECIFICATION SECTION 02200. ANY SETTLEMENT OCCURRING WITHIN ONE YEAR OF SUBSTANTIAL COMPLETION OF THE PROJECT WILL BE CORRECTED BY THE CONTRACTOR AT NO ADDITIONAL EXPENSE TO THE OWNER.
- 12. CONTRACTOR SHALL CONTROL DUST TO A TOLERABLE LIMIT AS OUTLINED IN SPECIFICATION SECTION 01562. CONTRACTOR SHALL NOT TRACK OR SPILL EARTH AND DEBRIS ON PUBLIC STREETS OUTSIDE THE PROJECT AREA. STREETS OPENED TO THE PUBLIC SHALL BE KEPT SWEPT AND FREE OF DEBRIS.
- 13. ALL VEGETATED AREAS ABOVE MEAN HIGH WATER ELEVATION THAT ARE EXCAVATED, FILLED OR OTHERWISE DISTURBED BY THE CONTRACTOR AND ARE NOT TO BE PAVED OR FILLED WITH RIPRAP SHALL BE LOAMED, GRADED, LIMED, FERTILIZED, SEEDED AND MULCHED AT NO ADDITIONAL EXPENSE TO THE OWNER.
- 14. THE CONTRACTOR SHALL BE RESPONSIBLE FOR RESETTING ALL EXISTING PROPERTY MONUMENTATION THAT IS DISTURBED BY HIS OPERATIONS AT NO EXPENSE TO THE OWNER. THIS WORK IS TO BE DONE BY A LAND SURVEYOR REGISTERED IN THE STATE OF MAINE.
- 15. THE CONTRACTOR SHALL COMPLY WITH ALL APPLICABLE REGULATIONS OF THE OCCUPATIONAL SAFETY AND HEALTH ADMINISTRATION (OSHA).
- 16. THE CONTRACTOR SHALL NOT HAVE ANY RIGHT OF PROPERTY IN ANY MATERIALS TAKEN FROM ANY EXCAVATION. SUITABLE EXCAVATED MATERIAL MAY BE INCORPORATED IN THE PROJECT, WITH EXCESS MATERIAL DISPOSED OF AT A LOCATION PROVIDED BY THE CONTRACTOR. THESE PROVISIONS SHALL IN NO WAY RELIEVE THE CONTRACTOR OF HIS OBLIGATIONS TO PROPERLY DISPOSE OF AND REPLACE ANY MATERIAL DETERMINED BY THE ENGINEER TO BE UNSUITABLE FOR BACKFILLING. THE CONTRACTOR SHALL DISPOSE OF UNSUITABLE AND EXCESS MATERIAL IN ACCORDANCE WITH THE APPLICABLE SECTIONS OF THE CONTRACT DOCUMENTS.

### **SITE GRADING NOTES**


- 1. ALL AREAS THAT ARE EXCAVATED, FILLED, OR OTHERWISE DISTURBED BY THE CONTRACTOR SHALL BE LOAMED, GRADED, LIMED, FERTILIZED, SEEDED AND MULCHED, UNLESS OTHERWISE NOTED. THE TOP 4 INCHES OF SOIL SHALL BE LOAM. REFER TO SPECIFICATION SECTION 02485, LANDSCAPING/LOAM AND SEED.
- 2. THE CONTRACTOR SHALL PROVIDE PROPER EROSION CONTROL AND DRAINAGE MEASURES IN ALL AREAS OF WORK, AND CONFINE SOIL SEDIMENT TO WITHIN THE LIMITS OF EXCAVATION AND GRADING. PRIOR TO BEGINNING EXCAVATION WORK, EROSION CONTROL FENCE SHALL BE INSTALLED AT THE DOWN GRADIENT PERIMETER OF THE ACTUAL LIMITS OF GRUBBING AND/OR GRADING, AND AS SHOWN ON THE DRAWINGS. EROSION CONTROL MEASURES SHOWN ON THE DRAWINGS ARE A MINIMUM, CONTRACTOR SHALL TAKE ALL OTHER NECESSARY MEASURES. EROSION CONTROL FENCE SHALL ALSO BE INSTALLED AT THE DOWN GRADIENT PERIMETER OF THE TOPSOIL STOCKPILES. ALL DISTURBED EARTH SURFACES SHALL BE STABILIZED IN THE SHORTEST PRACTICAL TIME AND TEMPORARY EROSION CONTROL DEVICES SHALL BE EMPLOYED UNTIL SUCH TIME AS ADEQUATE SOIL STABILIZATION HAS BEEN ACHIEVED. TEMPORARY STORAGE OF EXCAVATED MATERIAL SHALL BE STABILIZED IN A MANNER THAT WILL MINIMIZE EROSION. ALL INSTALLED EROSION CONTROL FACILITIES SHALL BE REMOVED AT THE END OF THE PROJECT. REFER TO SPECIFICATION SECTION 02270 AND EROSION CONTROL DETAILS DRAWING.
- 3. ALL MANHOLES AND OTHER BURIED FACILITIES WITH SURFACE ACCESS SHALL BE ADJUSTED TO MATCH FINAL GRADES, UNLESS OTHERWISE INDICATED.
- 4. CONTRACTOR SHALL REMOVE AND REPLACE, OR REPAIR, ALL CURBS, SIDEWALKS, PAVEMENT AND OTHER ITEMS DAMAGED BY HIS CONSTRUCTION ACTIVITIES TO AT LEAST THEIR ORIGINAL CONDITION, TO THE SATISFACTION OF THE OWNER AND ENGINEER.


### **SURVEY NOTES**

- 1. HORIZONTAL COORDINATE SYSTEM: ASSUMED NAD83 MAINE STATE PLANE, WEST ZONE, U.S. FOOT.
- 2. VERTICAL DATUM: NAVD88 DATUM
- 3. TOPOGRAPHIC SURVEY COMPLETED BY WRIGHT-PIERCE ON OCTOBER 14, 2014.
- 4. LOW TIDE OBSERVATION WAS TAKEN AT 10:03AM AND RECORDED AS 1.13' (MLW)
- 5. PROPERTY LINE INFORMATION IS APPROXIMATE (BASED ON TAX MAPPING AND ADJUSTED TO CORRESPOND TO MONUMENTATION FOUND).

CMP CORRUCATION MITTAL PIPE CO CLEANOUT CONC CONCRETE CO CLEANOUT CONCRETE CO CLEANOUT CONCRETE CO CONCRETE CONCRETE CO CONCRETE CONCRETE CO CONCRETE CONCRETE CONCRETE CO CONCRETE CONCRETE CO CONCRETE		BBREVIATIONS	<b>EXISTING</b>		PROPOSE
## DIAMETER ## STRACKLINE EASEMENT LINE ## CAPPO BAPROVED ## EASEMENT LINE ## CENTERINE ## CENTE				PROPERTY/ROW LINE	
IL NO NUMBER  APPORT DE PARROUED  CE CATCH BASIN  CONNEC CONCORTE  CONCORT  CONCORT	· ·			•	
EILDE GLOWER STATEMENT CONTRIBUTE	=		·		·
CEN CATCH BASIN CEN CENTER CEN CUBIC FET FER SCOND CI CAST RION CI CAS					
CEN C CENTER CON CONTROL CAST TRUE  CLEST CIBBLE EFF PER SECOND  CLEANOUT  COMP CORRECT  CON CORRET  CONC COR					
CAST IRON  CAST IRON  CAST IRON  COL  CLANOUT  CONCOCRETE  COC CLANOUT  CONC CONCRETE  COR CORRER  CORPER  CORRER  COR					
CL CENTREINE COMP CORNOLATED METAL PIPE CO CLEANOUT CONC CORRET CONC CORRET CONC CORRET COR CORNER CY CUBEVARION DEMOLITION DEMOLITI					74-974-974-974-974-974
CMP CORRUCATION MITTAL PIPE CO CLEANOUT CONC CONCRETE CO CLEANOUT CONCRETE CO CLEANOUT CONCRETE CO CONCRETE CONCRETE CO CONCRETE CONCRETE CO CONCRETE CONCRETE CONCRETE CO CONCRETE CONCRETE CO CONCRETE					<sup>4</sup> Δ Δ
CONCRETE CORRES CORRES CY CUBIC YARD DIAM DIAM MARANDIC DI DUCTIR IRON DI DI DUCTIR IRON DI DI DUCTIR IRON DI DI DUCTOR IRON DI DI DUCTOR IRON DI DI DUCT	СМР	CORRUGATED METAL PIPE	122		
COR CORNER CY CUBY YADD DEMO DEMOLITION DIME DAM MANHOLE DI DUCTILE IRON DI DU					<u> 123</u>
CUEIC YARD DEMO DEMO DEMO DEMO DEMO DEMO DEMO DEM					
DEMOULD DEMOUTH MARNOUS DEMOUTH DEMOUTH DEMOUTH DEMOUTH DEMOUTE DEMOUTH DEMOUT					~~~~~
DIR DRAIN DIR CRAIN DIR CR	DEMO	DEMOLITION	(YYYYY)		(YYYY)
DR DRAWN DOWN BARR WITE FENCE  ELEVATION RETAINING WALL  ELEVATION GUARDRAIL  FM FORCE MAIN  FF FET  G GAS  GAS  GAS  GAS  GAS  GAS  GAS  G		_	<del></del>		<del></del>
DAWE  EL ELEVATION ENH ELECTRIC MANHOLE EMH FOR EAS GAS GAS GAS HTD HYDRANT GAS GAS GAS GAS HTD HYDRANT GAS				STOCKADE FENCE	
EETHIC MANIFOLE  M FORCE MAIN  FT FEET  G GAS  GAS  GAS  GAS  HYD  HYDRANT  INCH  IN			X	BARB WIRE FENCE	<del></del>
FM FORCE MAIN  THE FET  G GAS  GAS  MN INCH  NE INCLENT  INV INVERT  LES POUNDS  MAX MAXIMUM  MINIMUM  MINIMUM  MINIMUM  MONTONINON WELL  N NORTH  NOVO  NAMONITONINON WELL  N NORTH  NOVO  NAMONITONINON WELL  N NORTH  NORYD  NAMONITONINON GEODETIC VERTICAL DATUM  NAJA  NOT AVAILABLE/APPILCABLE  TO STORE SEQUARE FOOT  PSP POUNDS PER SQUARE INCH  PSP POUNDS PER SQUAR			^	RETAINING WALL	
FT FEET G GAS G GAS HYD HYDRANT INCH INCH INCH INCH INCH INCH INCH INCH			0 0 0	GUARDRAIL	0 0
G AS  NTO MYDRANT NO INCH NNE INCLUENT NNA MAXIMUM MAXIMUM MAXIMUM MINIMUM MI				SEWER	<u>8"S</u>
INCH INFUENT INFUENT INVEST LES POUNDS INVEST INVEST LES POUNDS INVEST INVEST LES POUNDS INVEST INVES INVEST INVEST INVEST INVEST INVEST INVEST INVEST INVEST INVEST I			——————————————————————————————————————	SEWER FORCE MAIN	4"FM
INF INV INVERT INV INVERT INVE	HYD	HYDRANT	G	GAS	4"G
INV INVERT ILS POUNDS US US UNDERBRAIN MAX MAXIMUM MH MANIPOLE MIN MINIMUM MM MONITORING WELL N NORTH			W	WATER	8"W
NAX MAXIMUM MANHOLE UNDERGRAIN CULVERT CULVER			<u>15"</u> SD	STORM DRAIN	15"SD
MAXIMUM MH MANHOLE MIN MINIMUM MINIMUM MONOTIORING WELL N NORTH NOVD NORTH NORTH NORD NOT NORTH NORD NOT AVAILABLE/APPLICABLE NTS NOT TO SCALE OD OUTSIGE DIAMETER PF POUNDS PER SQUARE FOOT PS PRINAPY SLUDGE PT POINT OF TANGENCY PV PO'LVINIVL' CHIORDE RCP REINFORCED CONCRETE PIPE RD ROGO BRAIN RCQU RCP SSLOPE, SEWER SSLOPE, SEWER SSLOME SSLOPE, SEWER SMH SANTIARY SEWER MANHOLE SSLOPE, SEWER SMH SANTIARY SEWER MANHOLE SSLOPE, SEWER STA STATION TEMPORARY SEWICH MARK TEM TEMPORARY SEWICH MARK TEM TEMPORARY SEWICH MARK TEM TEMPORARY SEWICH MARK TEM TEMPORARY SEWICH MARK THK THICKNESS TOS TOP OF STRICTURE TYPY TYPICAL UID UNDERGROUND LECTRIC UID REGROUND UID REGROUN			6"		6 <u>"UD</u>
MANHOLE MINIMIMM MINIMIMM MINIMIMM MONITORING WELL NORTH NOVD NATIONAL GEODETIC VERTICAL DATUM N/A NATIONAL GEODETIC VERTI	MAX	MAXIMUM	12" CMP		1 <u>2" CMP</u>
MW MONTORING WELL N NORTH NORT					UGE
NORTH NGVD NATIONAL GEODETIC VERTICAL DATUM N/A NOT AVAILABLE/APPLICABLE NTS NOT TO SCALE OUTSIDE DIAMETER PC PERFORATED CLAV PS POUNDS PER SQUARE FOOT PS POUNDS PER SQUARE FOOT PS POUNDS PER SQUARE FOOT PS PS POUNDS PER SQU					
NATIONAL GEODETIC VERTICAL DATUM N/A N/A N/A N/A N/A N/A N/A NOT TO SCALE  D OUTSIDE DIAMETER PC PERFORATED CLAY PS POUNDS PER SQUARE FOOT PS PS POUNDS PER SQUARE INCH PS POUNDS PER SQUARE INCH PS PMAIN INCH PS POUNDS PER S					OHE
NOT NOT OS CALLE  OD OUTSIDE DIAMPETER  PC PERFORATED CLAY PSF POUNDS PER SQUARE POOT PSI POUNDS PER SQUARE NOT POUNDS PER SQUARE NOT POUNDS PER SQUARE NOT POUNDS PER SQUARE NOT PSI POUNDS PER SQUARE	NGVD	NATIONAL GEODETIC VERTICAL DATUM			
OUTSIDE DIAMETER PE PERFORATED CLAY PSF POUNDS PER SQUARE FOOT PSI POUNDS PER SQUARE FOOT PSI POUNDS PER SQUARE MICH PSF PRIMARY SLUDGE PT POINT OF TANGENCY PVC POLYVINVLCHIORIDE RCP REINFORCED CONCRETE PIPE RD ROOF DRAIN RCQ/D REQUIRED S SLOPE, SEWER S SLOPE, SEWER S SUAME RETET S SQUARE R					_
PER PONIOS PER SQUARE FOOT PSI POUNDS PER SQUARE INCH PS POUNDS PER SQUARE INCH PS POUNDS PER SQUARE INCH PS PRIMARY SLUDGE POUND POUNDS PER SQUARE INCH PS PRIMARY SLUDGE PRIMARY SLUDGE POLYVINYL CHLORIDE RCP REMPORCED CONCRETE PIPE RD ROOF DRAIN SEWER MANHOLE CATCH BASIN REQUE SUMPLIFIED PER ROW SOME PRIMARY SEWER MANHOLE SUMPLIFIED PER ROW SOME PRIMARY SEWER MANHOLE SUMPLIFIED PER ROW SANITARY SEWER MANHOLE SUMPLIFIED PER ROW SHIP SHOW SHIP SHIP SHOW SHIP SHOW SHIP SHOW SHIP SHOW SHIP SHIP SHOW SHIP SHIP SHIP SHIP SHIP SHIP SHIP SHIP					•
PSI POUNDS PER SQUARE NOT PSI POUNDS PER SQUARE NOT PSI POUNDS PER SQUARE NOT PSI PRIMARY SLUDGE PT POINT OF TANGENCY PVC POLYVINYL CHLORIDE RCP REINFORCED CONCRETE PIPE RD ROOF DRAIN SEWER MANHOLE DRAINAGE MANHOLE S SLOPE, SEWER STORM DRAIN SEWER MANHOLE S SLOPE, SEWER SANITARY SEWER MANHOLE SOL SQUARE FEET SITURE THE TEMPORARY SEWER MANHOLE SOL SQUARE STATION YARD HYDRANT TEMPORARY SEWCH MARK THICKNESS GAS SERVICE SHUTOFF TO THE TEMPORARY SENCH MARK THICKNESS GAS SERVICE SHUTOFF TO THE TEMPORARY SENCH MARK THE THICKNESS GAS SERVICE SHUTOFF TO TO FOR FITURITY POLE WITHITY POLE WITHI					•
PS PRIMARY SLUDGE PT POINT OF TANGENCY PVC QUYVINYL CHORIDE RCP REINFORCED CONCRETE PIPE RD ROOF DRAIN REQ'D REQUIRED S SLOPE, SEWER SANITARY SEWER MANHOLE SALOPE, SEWER SANITARY SEWER MANHOLE SALOPE, SEWER STA STATION T, XFMR TRANSFORMER STA STATION T, XFMR TRANSFORMER THICKNESS STOOP OF STRUCTURE TOP OF STRUCTURE UD UNDERGROUND UGE UNDERGROUND ELECTRIC VC VITIRIFIED CLAP W/WITH W POTABLE WATER  POTABLE WATER  SPOT ELEVATION SEWER MANHOLE DRAINANGE MANHOLE SEWER MANHOLE DRAINANGE MANHOLE SEWER MANHOLE DRAINANGE MANHOLE SEWER MANHOLE DRAINANGE MANHOLE SEWER MANHOLE CATCH BASIN ELECTRIC MANHOLE SHUTOFF VALVE WATER SERVICE SHUTOFF YARD HYDRANT HYBRANT HYBRANHOLE DRAINAGE MANHOLE DRAINAGE SHUTOFF HYBRANT HYBRANT HYBRANT HYBRANT HYBRANHOLE DRAINAGE MANHOLE DRAINAGE MAN				MONUMENT	•
PT POINT OF TANGENCY PVC POLYVINYL CHLORIDE RCP REINFORCED CONCRETE PIPE RD ROOF DRAIN RCQD S SLOPE, SEWER SD STORM DRAIN SF SQUARE FET SM SANITARY SEWER MANHOLE SQ SQUARE STA STATION TEMPORARY SENCH MARK THK THICKNESS TOS TOP OF STRUCTURE TVP TYPICAL UD UNDERGROUND ELECTRIC UGE UNDERGROUND ELECTRIC VC VITRIFIED CLAY W//			$\triangle$	SURVEY CONTROL POINT	
PVC POLYVINYL CHLORIDE RCP REINFORCED CONCRETE PIPE RD ROOF DRAIN REQ'D REQUIRED S SLOPE, SEWER SD STORM DRAIN SF SQUARE FETT SMH SANITARY SEWER MANHOLE SQ SQUARE STA STATION T, XFMR TRANSFORMER TIEM TEMPORARY BENCH MARK THK THICKNESS TOS TOP OF STRUCTURE TYP TYPICAL UD UNDERGROUND UGE UNDERGROUND UGE UNDERGROUND ELECTRIC WY WITH W POTABLE WATER  POTABLE WATER  STREAM POTABLE WATER  DECIDIOUS TREE DECIDIOUS				SPOT ELEVATION	x <sup>134.5</sup>
RCP REINFORCED CONCRETE PIPE RD ROOF DRAIN REQUIRED S SLOPE, SEWER SD STORM DRAIN SF SQUARE FEET SQUARE STA STATION T, XFMR TRANSFORMER TEMPORARY BENCH MARK THK THICKNESS TOS TOP OF STRUTURE UD UNDERGROUND UGE UNDERGROUND UGE UNDERGROUND UG UNDERGROUND UTILITY POLE W/ LIGHT U				SEWER MANHOLE	■ SMH
S SLOPE, SEWER  STORM DRAIN  SOUARE FEET  SUJURE FEET  SHUTOFF VALVE  SMH SANITARY SEWER MANHOLE SQ SQUARE STA STATION  T, XFMR TRANSFORMER  THANSFORMER  THEMPORARY BENCH MARK  THK THICKNES  TOP OF STRUCTURE  TYP TYPICAL  UD UNDERGROUND  UGE UNDERGROUND  UGE UNDERGROUND LELECTRIC  VV VITIFIED CLAY  WITH  W POTABLE WATER  TEMPORARY  THEMPORARY  THEMPORA			$\bigcirc$	DRAINAGE MANHOLE	● DMH
S SLOPE, SEWER  STORM DRAIN  SOUARE FEET  SUJURE FEET  SHUTOFF VALVE  SMH SANITARY SEWER MANHOLE SQ SQUARE STA STATION  T, XFMR TRANSFORMER  THANSFORMER  THEMPORARY BENCH MARK  THK THICKNES  TOP OF STRUCTURE  TYP TYPICAL  UD UNDERGROUND  UGE UNDERGROUND  UGE UNDERGROUND LELECTRIC  VV VITIFIED CLAY  WITH  W POTABLE WATER  TEMPORARY  THEMPORARY  THEMPORA				<b>CATCH BASIN</b>	●СВ ■СВ
SD STORM DRAIN  SF SQUARE FEET  SMH SANITARY SEWER MANHOLE  SQ SQUARE  STATION  TEMPORARY BENCH MARK  THICKNESS  TOS TOP OF STRUCTURE  UD UNDERGROUND  UGE UNDERGROUND  UGE UNDERGROUND  UGE UNDERGROUND  UGE UNDERGROUND  UFF PALAGPOLE  VC VITRIFIED CLAY  WITH  W POTABLE WATER  DECIDUOUS TREE  DECIDUOUS				ELECTRIC MANHOLE	<b>■</b> EMH
SF SQUARE FEET WATER SERVICE SHUTOFF VALVE SMH SANITARY SEWER MANHOLE SQ SQUARE STA STATION TEMPORARY BENCH MARK TEMPORARY BENCH MARK THIK THICKNESS TOS TOP OF STRUCTURE TYP TYPICAL UD UNDERGROUND UGE UNDERGROUND UGE UNDERGROUND ELECTRIC VITILITY POLE W/ LIGHT VIT VITRIFIED CLAY W/ WITH W POTABLE WATER  POTABLE WATER  A WETLAND FLAG EDGE OF WETLANDS FLOODPLAIN WETLANDS DRAINAGE SWALE PAVEMENT MARKINGS SIGN MAILBOX TEMPORARY BENCH MARK TEST PIT TEST POBRE MONITORING WELL LIMIT OF WORK SILT FENCE MIND MONITORING WELL LIMIT OF WORK SILT FENCE MIND MONITORING WELL LIMIT OF WORK SILT FENCE RIPRAP			TMH ☐ ○	TELEPHONE MANHOLE	<b>■</b> TMH
SMIH SANITARY SEWER MANHOLE SQ SQUARE STA STATION TRANSFORMER TEMPORARY BENCH MARK THICKNESS TOS TOP OF STRUCTURE TYP TYPICAL UD UNDERGROUND UGE UNDERGROUND ELECTRIC VC VITRIFIED CLAY W/ WITH W POTABLE WATER  DECIDIOUS TREE SHRUB  WETLAND FLAG EDGE OF WATER SHRUB  WETLAND FLAG EDGE OF WATER SHRUB  DRAINAGE FLOW DRAINAGE SWALE PAVEMENT MANIBOX TEMPORARY BENCH MARK THICKNESS TOS TOP OF STRUCTURE TYP TYPICAL UD UNDERGROUND UGE UNDERGROUND UTILITY POLE W/ GUY UTILITY POLE W/ GUY UTILITY POLE W/ GUY UTILITY POLE W/ GUY UTILITY POLE W/ LIGHT UTILITY POLE W/ LIGHT UTILITY POLE W/ GUY UTILITY POLE UTILITY  GAS SERVICE SATEWARY UTILITY POLE UTILITY POLE UTILITY POLE UTILITY POLE UTILI			$\bowtie$	SHUTOFF VALVE	H
SQ SQUARE STA STATION T, XFMR TRANSFORMER TRANSFORMER TREMPORARY BENCH MARK THICKNESS TOS TOP OF STRUCTURE TYP TYPICAL UD UNDERDRAIN UGE UNDERGROUND ELECTRIC VC VITRIFIED CLAY W/ WITH W POTABLE WATER  GENEROUS TREE GENEROUS TR					8
T, XFMR TRANSFORMER TEMPORARY BENCH MARK THICKNESS TOF OF STRUCTURE TYP TYPICAL UD UNDERGRAIN UG UNDERGROUND UGE UNDERGROUND ELECTRIC VC VITRIFIED CLAY W/ WITH W POTABLE WATER  DECIDUOUS TREE SHRUB WETLAND FLAG EDGE OF WATER  TEST PIT TEST PIT TEST PIT TEST PIT TEST PIT TEST PIT TEST POBE MW MONITORING WELL LIMIT OF WORK SILT FENCE MW MONITORING WELL LIMIT OF WORK SILT FENCE RIPRAP					*
TBM TEMPORARY BENCH MARK THIK THICKNESS TOP OF STRUCTURE TYP TYPICAL UD UNDERGROUND UGE UNDERGROUND UGE UNDERGROUND UGE UNDERGROUND ELECTRIC VC VITRIFIED CLAY W/ WITH W POTABLE WATER  POTABLE WATER  GAS SERVICE SHUTOFF GAS GATE VALVE UTILITY POLE UTILITY POLE W/ GUY UTILITY POLE W/ LIGHT LIGHT POLE BOLLARD FLAGPOLE CONIFEROUS TREE DECIDUOUS TREE SHRUB WETLAND FLAG EDGE OF WATER STREAM EDGE OF WATER STREAM EDGE OF WETLANDS DRAINAGE FLOW DRAINAGE FLOW DRAINAGE FLOW DRAINAGE SWALE PAVEMENT MARKINGS SIGN MAILBOX TEMPORARY BENCH MARK TEST PIT TEST PROBE MONITORING WELL LIMIT OF WORK SILT FENCE RIPRAP					
THK THICKNESS TOS TOP OF STRUCTURE TYP TYPICAL UD UNDERBRAIN UG UNDERBROUND UGE UNDERGROUND ELECTRIC VC VITRIFIED CLAY W/ WITH W POTABLE WATER  DECIDUOUS TREE SHRUB WETLAND FLAG EDGE OF WATER STREAM EDGE OF WATER STREAM EDGE OF WATER STREAM PAVEMENT MARKINGS SIGN MAILBOX TEMPORARY BENCH MARK TEST PIT TEST PROBE MONITORING WELL LIMIT OF WORK SILT FENCE RIPRAP					•
TYP TYPICAL  UD UNDERDRAIN  UG UNDERGROUND  UGE UNDERGROUND ELECTRIC  VC VITRIFIED CLAY  W WITH  W POTABLE WATER  PLAGPOLE  CONIFEROUS TREE  DECIDUOUS TREE  SHRUB  WETLAND FLAG  EDGE OF WATER  STREAM  EDGE OF WETLANDS  DRAINAGE FLOW  DRAINAGE FLOW  DRAINAGE FLOW  DRAINAGE SWALE  PAVEMENT MARKINGS  SIGN  MAILBOX  TEMPORARY BENCH MARK  TEST PIT  B TEST PIT  B TEST PROBE  MONITORING WELL  LIMIT OF WORK  SILT FENCE  RIPRAP					
UD UNDERGROUND UGE UNDERGROUND USE UNDERGROUND ELECTRIC VC VITRIPIED CLAY W/ WITH W POTABLE WATER  BOLLARD FLAGPOLE CONIFEROUS TREE DECIDUOUS TREE SHRUB  WETLAND FLAG EDGE OF WATER  STREAM EDGE OF WETLANDS FLOODPLAIN WETLANDS DRAINAGE FLOW DRAINAGE FLOW DRAINAGE SWALE PAVEMENT MARKINGS SIGN MB MAILBOX TEMPORARY BENCH MARK TEST PIT TEST PIT TEST PIT TEST PROBE MM MONITORING WELL LIMIT OF WORK SILT FENCE RIPRAP					ø
UG UNDERGROUND UGE UNDERGROUND ELECTRIC VC VITRIFIED CLAY W/ WITH W POTABLE WATER  DECIDUOUS TREE DECIDUOUS TREE SHRUB  WETLAND FLAG EDGE OF WATER  STREAM EDGE OF WETLANDS FLOODPLAIN WETLANDS DRAINAGE FLOW DRAINAGE FLOW DRAINAGE FLOW DRAINAGE SWALE PAVEMENT MARKINGS SIGN MAILBOX TEMPORARY BENCH MARK TEST PIT TEST PIT TEST PIT TEST PROBE MONITORING WELL LIMIT OF WORK SILT FENCE RIPRAP			, <u>/</u>		
USE UNDERGROUND LECTRIC VC VITRIFIED CLAY W/ WITH V POTABLE WATER  BOLLARD FLAGPOLE CONIFEROUS TREE DECIDUOUS TREE SHRUB WETLAND FLAG EDGE OF WATER STREAM EDGE OF WETLANDS FLOODPLAIN WETLANDS DRAINAGE FLOW DRAINAGE FLOW DRAINAGE SWALE PAVEMENT MARKINGS SIGN MAILBOX TEMPORARY BENCH MARK TEST PIT TEST PIT TEST POBE MONITORING WELL LIMIT OF WORK SILT FENCE RIPRAP			, ±X	•	<b>*</b>
W/ WITH POTABLE WATER  BOLLARD FLAGPOLE CONIFEROUS TREE DECIDUOUS TREE SHRUB WETLAND FLAG EDGE OF WATER STREAM EDGE OF WETLANDS FLOODPLAIN WETLANDS DRAINAGE FLOW DRAINAGE SWALE PAVEMENT MARKINGS SIGN MB MAILBOX TEMPORARY BENCH MARK TEST PIT TEST PIT B TEST PROBE MM MONITORING WELL LIMIT OF WORK SILT FENCE RIPRAP			~	·	7
POTABLE WATER  POTABL					*
FLAGPOLE  CONIFEROUS TREE  DECIDUOUS TREE  SHRUB  WETLAND FLAG  EDGE OF WATER  STREAM  EDGE OF WETLANDS  FLOODPLAIN  WETLANDS  DRAINAGE FLOW  DRAINAGE FLOW  DRAINAGE SWALE  PAVEMENT MARKINGS  SIGN  MAILBOX  TEST PIT  TEST PIT  TEST PROBE  MONITORING WELL  LIMIT OF WORK  SILT FENCE  RIPRAP			0	BOLLARD	•
DECIDUOUS TREE SHRUB  WETLAND FLAG EDGE OF WATER STREAM EDGE OF WETLANDS FLOODPLAIN WETLANDS DRAINAGE FLOW DRAINAGE SWALE PAVEMENT MARKINGS SIGN MAILBOX TEMPORARY BENCH MARK TEST PIT TEST PIT TEST PIT TEST PROBE MONITORING WELL LIMIT OF WORK SILT FENCE RIPRAP			○ <b>~</b>	FLAGPOLE	~ .v
SHRUB  WETLAND FLAG EDGE OF WATER STREAM  EDGE OF WETLANDS FLOODPLAIN WETLANDS DRAINAGE FLOW DRAINAGE SWALE PAVEMENT MARKINGS SIGN MAILBOX TEMPORARY BENCH MARK TEST PIT TEST PIT B TEST PROBE MW MONITORING WELL LIMIT OF WORK SILT FENCE RIPRAP				CONIFEROUS TREE	7
WETLAND FLAG EDGE OF WATER STREAM  EDGE OF WETLANDS FLOODPLAIN WETLANDS DRAINAGE FLOW DRAINAGE SWALE PAVEMENT MARKINGS SIGN MAILBOX TEMPORARY BENCH MARK TEST PIT TEST PIT TEST PROBE MONITORING WELL LIMIT OF WORK SILT FENCE RIPRAP			£ 3	DECIDUOUS TREE	
WETLAND FLAG EDGE OF WATER STREAM  EDGE OF WETLANDS FLOODPLAIN WETLANDS DRAINAGE FLOW DRAINAGE SWALE PAVEMENT MARKINGS SIGN MAILBOX TEMPORARY BENCH MARK TEST PIT TEST PIT TEST PROBE MONITORING WELL LIMIT OF WORK SILT FENCE RIPRAP			$\Box$	SHRUB	<b>C</b>
EDGE OF WATER  STREAM  EDGE OF WETLANDS  FLOODPLAIN  WETLANDS  DRAINAGE FLOW  DRAINAGE SWALE  PAVEMENT MARKINGS  SIGN  MB  MAILBOX  TEMPORARY BENCH MARK  TEST PIT  TEST PIT  TEST PROBE  MONITORING WELL  LIMIT OF WORK  SILT FENCE  RIPRAP				WETLAND FLAG	
EDGE OF WETLANDS  FLOODPLAIN  WETLANDS  DRAINAGE FLOW  DRAINAGE SWALE  PAVEMENT MARKINGS  SIGN  MAILBOX  TEMPORARY BENCH MARK  TEST PIT  TEST PIT  TEST POBE  MW  MONITORING WELL  LIMIT OF WORK  SILT FENCE  RIPRAP					
EDGE OF WETLANDS  FLOODPLAIN  WETLANDS  DRAINAGE FLOW  DRAINAGE SWALE  PAVEMENT MARKINGS  SIGN  MAILBOX  TEMPORARY BENCH MARK  TEST PIT  TEST PIT  TEST POBE  MW  MONITORING WELL  LIMIT OF WORK  SILT FENCE  RIPRAP				STREAM	
FLOODPLAIN WETLANDS DRAINAGE FLOW DRAINAGE SWALE PAVEMENT MARKINGS SIGN MB MAILBOX TEMPORARY BENCH MARK TEST PIT TEST PIT B TEST BORING P TEST PROBE MW MONITORING WELL LIMIT OF WORK SILT FENCE RIPRAP					
WETLANDS  DRAINAGE FLOW  DRAINAGE SWALE  PAVEMENT MARKINGS  SIGN  MB  MAILBOX  TEMPORARY BENCH MARK  TP  TEST PIT  B  TEST BORING  P  TEST PROBE  MW  MONITORING WELL  LIMIT OF WORK  SILT FENCE  RIPRAP					
DRAINAGE FLOW DRAINAGE SWALE PAVEMENT MARKINGS SIGN MAILBOX TEMPORARY BENCH MARK TEST PIT B TEST POBE MW MONITORING WELL LIMIT OF WORK SILT FENCE RIPRAP			<u> 11/4</u>		
DRAINAGE SWALE  PAVEMENT MARKINGS  SIGN  MB  MAILBOX  TEMPORARY BENCH MARK  TEST PIT  B  TEST BORING  TEST PROBE  MW  MONITORING WELL  LIMIT OF WORK  SILT FENCE  RIPRAP					
PAVEMENT MARKINGS  SIGN  MB  MAILBOX  TEMPORARY BENCH MARK  TEST PIT  B  TEST BORING  P  TEST PROBE  MW  MONITORING WELL  LIMIT OF WORK  SILT FENCE  RIPRAP			$\rightarrow$		<b>-</b>
SIGN  MAILBOX  TEMPORARY BENCH MARK  TEST PIT  TEST BORING  P TEST PROBE  MW MONITORING WELL  LIMIT OF WORK  SILT FENCE  RIPRAP			—		
TEMPORARY BENCH MARK  TEST PIT  B TEST BORING  TEST PROBE  MW MONITORING WELL  LIMIT OF WORK  SILT FENCE  RIPRAP			<b>-</b> 6		<b>→</b> &
TEMPORARY BENCH MARK  TEST PIT  B TEST BORING  TEST PROBE  MW MONITORING WELL  LIMIT OF WORK  SILT FENCE  RIPRAP					
TP TEST PIT  B B TEST BORING  TEST PROBE  MW MONITORING WELL  LIMIT OF WORK  SILT FENCE  RIPRAP			□ <sup>MB</sup>		
B TEST BORING TEST PROBE  MW MONITORING WELL  LIMIT OF WORK  SILT FENCE  RIPRAP				TEMPORARY BENCH MARK	
TEST PROBE  MW MONITORING WELL  LIMIT OF WORK  SILT FENCE  RIPRAP			TP	TEST PIT	
MW MONITORING WELL  LIMIT OF WORK  SILT FENCE  RIPRAP			$lackbox{}^{B}$	TEST BORING	
LIMIT OF WORK  SILT FENCE  RIPRAP			P	TEST PROBE	
LIMIT OF WORK  SILT FENCE  RIPRAP			• MW	MONITORING WELL	
SILT FENCE				LIMIT OF WORK	
RIPRAP					×
RANKIAN				RAILROAD	K AIRY A RY
MATCHLINE —					
ROCK OUTCROP			/XX		

**DRAWING C-1** 






F-PIERCE ng a Better Enviro

DRAWING


**C-4** 



**OUTFALL** 

**PROFILE** 

SCALE VERT: 1"=10' HORIZ: 1"=10'




**C-6** 

### RIPRAP SLOPE PROTECTION

1. PLACE RIPRAP AT 1.5:1(HORIZONTAL:VERTICAL) SLOPE MAXIMUM.

- 2. TOE OF SLOPE RIPRAP SHOULD BE KEYED INTO THE EXISTING GROUND SURFACE A MINIMUM OF 3'-0".
- 3. A NON-WOVEN GEOTEXTILE FILTER FABRIC (MIRAFI 140N OR EQUIVALENT) SHOULD BE INSTALLED OVER SUBGRADE PRIOR TO PLACING RIPRAP. THE FILTER FABRIC SHOULD OVERLAP THE TOP OF THE RIPRAP.
- 4. WHERE REQUIRED, GRANULAR BORROW SHOULD BE PLACED IN 12" THICK LIFTS AND COMPACTED TO 92% OF IT'S MAXIMUM DRY DENSITY PER ASTM D-698 (STANDARD PROCTOR).



- (A) INDICATES BODKIN CONNECTION USING 3/8" DIAMETER HDPE BODKIN ROD
- B INDICATES BRAIDED SEAM USING 3/16" DIAMETER HIGH UV HDPE BRAID

### NOTES:

ENDS, TOP, BOTTOM, SIDES AND ANY EXTRA LENGTH USED FOR LIFTING OR ANCHORING PURPOSES SHALL BE COMPOSED OF TENSAR UXTRITON 200 GEOGRID.

INTERNAL DIAPHRAGMS SHALL BE COMPOSED OF TENSAR UXTRITON 100 GEOGRID.


NOMINAL WIDTH OF UNITS: 5FT (FILLED), 4.3 FT (UNFILLED).

TYPICAL THICKNESS (FILLED): 12 INCHES; OPTIONAL THICKNESS: 18 INCHES OR 24 INCHES.

PLASTIC CABLES TIES MAY BE USED TO SECURE BODKIN CONNECTORS IN POSITION PRIOR TO TENSIONING OR FILLING OF MATTRESS UNITS.

MATTRESS STONE FILL SHALL BE D50 = 4" RIPRAP. NO STONES LARGER THAN 6" OR SMALLER THAN 2" SHALL BE USED AS STONE FILL.

# REVETMENT MATTRESS DETAIL SCALE: NTS



ALL CUT ENDS OF BRAID MATERIAL SHALL BE KNOTTED WITHIN 1/2" TO 2" OF THE END TO PREVENT RAVELING OF BRAID.

AT ALL ENDS OF ALL BRAIDED SEAMS THE BRAID SHALL BE SECURELY KNOTTED TO THE GEOGRID.


AT ALL ENDS OF ALL PIECES OF BRAID MATERIAL USED, THE BRAID SHALL BE KNOTTED TO SPLICE IT TO THE NEXT PIECE OF BRAID, OR TO SECURE IT TO THE GEOGRID. EACH BRAIDED SEAM SHALL BE CONTINUOUS, WITH SECURELY KNOTTED SPLICES ALLOWED. THE BRAID SHALL BE SECURELY KNOTTED TO THE GEOGRID AT A SPACING NOT TO EXCEED 6 FT ALONG ANY SEAM.

THE BRAID SHALL BE STITCHED THROUGH EACH PAIR OF APERTURES ALONG THE SEAM AT LEAST ONCE, AND THE MINIMUM NUMBER OF STITCHES PER FOOT ALONG THE SEAM SHALL BE SIX (6). THE SPACING OF STITCHES ALONG EACH SEAM SHALL BE REASONABLY UNIFORM.


ALL KNOTS SHALL BE TIED IN A MANNER TO PREVENT SLIPPING AND CINCHING.

THE WRAPS ALONG THE SEAM SHALL BE SUFFICIENTLY TIGHT TO CLOSE THE GAP BETWEEN THE ADJACENT PIECES OF GEOGRID, BUT SHALL NOT BE OVER-TIGHTENED SUCH THAT THE GEOGRID BINDS ALONG THE SEAM.


REVETMENT MATTRESS CONNECTION DETAIL



### TYPICAL DRIVE SECTION




# PAVEMENT SECTION SCALE: NTS




- 1. USE NEENAH R-4341-A OR EQUIVALENT GRATE.
- 2. USE NEENAH R-1924 OR EQUIVALENT FRAME.


# DITCH GRATE



# FRAME AND COVER FOR TYPE "A" CATCH BASIN



# CATCH BASIN SCALE: NTS




NOTES:


1. ALL EXCAVATION MUST MEET OSHA STANDARDS.

- 2. INSTALL 3 FOOT LONG IMPERVIOUS MATERIAL DAM IN BEDDING/INITIAL BACKFILL MATERIAL EVERY 100' AND WHERE SHOWN ON PLANS TO PREVENT TRENCH GROUNDWATER FROM BEING CHANNELED ALONG BEDDING/INITIAL BACKFILL.
- 3. SEE SPECIFICATIONS FOR BEDDING AND BACKFILL REQUIREMENTS.

PIPE TRENCH
SCALE: "NTS"



# DRAIN MANHOLE STANDARD COVER AND FRAME



FLAT SLAB TOP DRAIN MANHOLE

SCALE: "NTS"

DRAWIN C-7

WRIGHT

UNDERWOOD ROAD
DRAINAGE IMPROVEMENTS
FALMOUTH, MAINE

DRAWING

THE PROPOSED LOCATIONS OF SILTATION AND EROSION CONTROL STRUCTURES ARE SHOWN ON THE SITE PLAN.

- ALL SEDIMENT AND EROSION CONTROL MEASURES SHALL BE DONE IN ACCORDANCE WITH 2014 REVISION TO THE 2003 MAINE EROSION AND SEDIMENT CONTROL FIELD GUIDE FOR CONTRACTORS. ALL TEMPORARY MEASURES SHALL NOT BE REMOVED **UNTIL SITE IS FULLY STABILIZED.**
- IN AREAS ADJACENT TO NATURAL RESOURCES, LOCATIONS TO BE VEGETATED IN THEIR FINISH CONDITION SHALL BE STABILIZED WITH MULCH WITHIN 7 DAYS OF DISTURBANCE.
- 3. AREAS THAT WILL NOT RECEIVE FINAL GRADING FOR UP TO ONE YEAR SHALL BE STABILIZED WITH MULCH WITHIN 7 DAYS OF
- 4. THOSE AREAS UNDERGOING ACTUAL CONSTRUCTION WILL BE MAINTAINED IN AN UNTREATED OR UNVEGETATED CONDITION FOR THE MINIMUM TIME REQUIRED. IN GENERAL AREAS TO BE VEGETATED SHALL BE PERMANENTLY STABILIZED WITHIN 15 DAYS OF FINAL GRADING AND TEMPORARILY STABILIZED WITHIN 30 DAYS OF INITIAL DISTURBANCE OF THE SOIL.
- 5. SEDIMENT BARRIERS (SILT FENCE, STONE CHECK DAMS, ETC.) SHOULD BE INSTALLED PRIOR TO ANY SOIL DISTURBANCE OF **UPGRADIENT DRAINAGE AREAS.**
- 6. INSTALL SILT FENCE AT TOE OF SLOPES TO FILTER SILT FROM RUNOFF. SEE SILT FENCE DETAIL FOR PROPER INSTALLATION. SILT FENCE WILL REMAIN IN PLACE PER NOTE #5.
- 7. ALL EROSION CONTROL STRUCTURES WILL BE INSPECTED, REPLACED AND/OR REPAIRED EVERY 7 DAYS AND IMMEDIATELY FOLLOWING ANY SIGNIFICANT RAINFALL OR SNOW MELT OR WHEN NO LONGER SERVICEABLE DUE TO SEDIMENT ACCUMULATION OR DECOMPOSURE. IF REPAIRS ARE IDENTIFIED, THEY SHALL BEGIN NO LATER THAN THE END OF THE FOLLOWING WORK DAY AND BE COMPLETE WITHIN 7 DAYS FROM INSPECTION. SEDIMENT DEPOSITS MUST BE REMOVED WHEN THEY REACH APPROXIMATELY ONE HALF THE HEIGHT OF THE BARRIER. SEDIMENT CONTROL DEVICES SHALL REMAIN IN PLACE AND BE MAINTAINED BY THE CONTRACTOR UNTIL AREAS UPSLOPE ARE PERMANENTLY STABILIZED.
- NO SLOPES, EITHER PERMANENT OR TEMPORARY, SHALL BE STEEPER THAN TWO HORIZONTAL TO ONE VERTICAL (2 TO 1) UNLESS STABILIZED WITH RIPRAP OR OTHER STRUCTURAL MEANS. NO SLOPES IN EXCESS OF 1.5H:1V SHALL BE ALLOWED.
- 9. IF FINAL SEEDING AND SODDING IS NOT EXPECTED PRIOR TO THE ANTICIPATED DATE OF THE FIRST KILLING FROST, USE TEMPORARY ANNUAL RYEGRASS SEEDING AND MULCHING ON ROUGH GRADED SUBSOIL TO PROTECT THE SITE AND DELAY PERMANENT LOAMING, FINE GRADING, AND SEEDING OR SODDING UNTIL SPRING.
- 10. WHEN FEASIBLE, TEMPORARY SEEDING OF DISTURBED AREAS THAT HAVE NOT BEEN FINISH GRADED SHALL BE COMPLETED 30 DAYS PRIOR TO THE FIRST KILLING FROST.
- 11. DURING THE CONSTRUCTION PHASE, INTERCEPTED SEDIMENT WILL BE RETURNED TO THE SITE AND REGRADED ONTO OPEN AREAS. POST SEEDING SEDIMENT, IF ANY, WILL BE DISPOSED OF IN AN ACCEPTABLE MANNER.
- 12. REVEGETATION MEASURES WILL COMMENCE UPON COMPLETION OF CONSTRUCTION EXCEPT AS NOTED ABOVE. ALL DISTURBED AREAS NOT OTHERWISE STABILIZED WILL BE GRADED, SMOOTHED, AND REVEGETATED.
- 13. ALL TEMPORARY EROSION CONTROL MEASURES SHALL BE REMOVED ONCE THE SITE IS STABILIZED
- 14. EXCAVATION AND EARTHWORK SHALL BE DONE SUCH THAT NO MORE THAN 1 ACRE OF THE SITE IS WITHOUT STABILIZATION AT ANY ONE TIME.
- 15. EXPOSED AREA SHOULD BE LIMITED SUCH THAT THE AREA CAN BE MULCHED IN ONE DAY PRIOR TO ANY SNOW EVENT.
- 16. STABILIZATION SCHEDULE BEFORE WINTERS

<b>SEPTEMBER 15</b>	ALL DISTURBED AREAS MUST BE SEEDED AND MULCHED.
	ALL SLOPES MUST BE STABILIZED SEEDED AND MULCHEL

SLOPES 3:1 OR GREATER TO BE STABILIZED WITH EROSION CONTROL MATTING AND SEEDED. ALL DISTURBED AREAS TO BE PROTECTED WITH AN ANNUAL GRASS MUST BE SEEDED AT A SEEDING RATE OF 3 POUNDS PER 1,000 SQUARE FEET AND MULCHED.

OCTOBER 1 ALL GRASS-LINED DITCHES AND CHANNELS MUST BE STABILIZED WITH MULCH OR EROSION

CONTROL BLANKET.

ALL STONE-LINED DITCHES AND CHANNELS MUST BE CONSTRUCTED AND STABILIZED. SLOPES THAT ARE COVERED WITH RIPRAP MUST BE CONSTRUCTED BY THAT DATE.

ALL DISTURBED AREAS WHERE THE GROWTH OF VEGETATION FAILS TO BE AT LEAST THREE INCHES

TALL OR AT LEAST 75% OF THE DISTURBED SOIL IS COVERED BY VEGETATION, MUST BE PROTECTED FOR OVER-WINTER.

- 17. SEDIMENT BARRIERS SHALL BE INSTALLED DOWNGRADIENT OF STOCKPILES, AND STORMWATER SHALL BE PREVENTED FROM
- 18. CONTRACTOR SHALL MAINTAIN ALL STABILIZED CONSTRUCTION ENTRANCES UNTIL ALL DISTURBED AREAS ARE STABILIZED.
- 19. MULCH MAY REQUIRE ANCHORING TO ENSURE THAT MULCH REMAINS IN-PLACE. MULCH NETTING, CRIMPING, OR PUNCHING ARE ACCEPTABLE METHODS. MULCH NETTING SHALL BE TENAX RADIX EROSION CONTROL NETS OR APPROVED EQUAL, AND SHALL BE INSTALLED IN ACCORDANCE WITH MANUFACTURER REQUIREMENTS.
- 20. SPILL PREVENTION: CONTROLS MUST BE USED TO PREVENT POLLUTANTS FROM BEING DISCHARGED FROM MATERIALS AND EQUIPMENT ON-SITE, INCLUDING STORAGE PRACTICES TO MINIMIZE EXPOSURE OF THE MATERIALS TO STORMWATER, AND APPROPRIATE SPILL PREVENTION. CONTAINMENT, AND RESPONSE PLANNING AND IMPLEMENTATION.
- 21. GROUNDWATER PROTECTION: DURING CONSTRUCTION, LIQUID PETROLEUM PRODUCTS AND OTHER HAZARDOUS MATERIALS WITH THE POTENTIAL TO CONTAMINATE GROUNDWATER MAY NOT BE STORED OR HANDLED IN AREAS OF THE SITE DRAINING TO AN INFILTRATION AREA. AN "INFILTRATION AREA" IS ANY AREA OF THE SITE THAT BY DESIGN OR AS A RESULT OF SOILS, TOPOGRAPHY AND OTHER RELEVANT FACTORS, ACCUMULATES RUNOFF THAT INFILTRATES INTO THE SOIL. DIKES, BERMS, SUMPS, AND OTHER FORMS OF SECONDARY CONTAINMENT THAT PREVENT DISCHARGE TO GROUNDWATER MAY BE USED TO ISOLATE PORTIONS OF THE SITE FOR THE PURPOSES OF STORAGE AND HANDLING OF THESE MATERIALS.
- 22. MINIMIZE THE EXPOSURE OF CONSTRUCTION DEBRIS, BUILDING AND LANDSCAPING MATERIALS, TRASH, FERTILIZERS, PESTICIDES, HERBICIDES, DETERGENTS, SANITARY WASTE AND OTHER MATERIALS TO PRECIPITATION AND STORMWATER RUNOFF. THESE MATERIALS MUST BE PREVENTED FROM BECOMING A POLLUTANT SOURCE.
- 23. EXCAVATION DE-WATERING IS THE REMOVAL OF WATER FROM TRENCHES, FOUNDATIONS, COFFER DAMS, PONDS, AND OTHER AREAS WITHIN THE CONSTRUCTION AREA THAT RETAIN WATER AFTER EXCAVATION. IN MOST CASES THE COLLECTED WATER IS HEAVILY SILTED AND HINDERS CORRECT AND SAFE CONSTRUCTION PRACTICES. THE COLLECTED WATER REMOVED FROM THE PONDED AREA. EITHER THROUGH GRAVITY OR PUMPING. MUST BE SPREAD THROUGH NATURAL WOODED BUFFERS OR REMOVED TO AREAS THAT ARE SPECIFICALLY DESIGNED TO COLLECT THE MAXIMUM AMOUNT OF SEDIMENT POSSIBLE, LIKE A COFFERDAM SEDIMENTATION BASIN. AVOID ALLOWING THE WATER TO FLOW OVER DISTURBED AREAS OF THE SITE. **EQUIVALENT MEASURES MAY BE TAKEN IF APPROVED BY THE DEPARTMENT.**
- AUTHORIZED NON-STORMWATER DISCHARGES: IDENTIFY AND PREVENT CONTAMINATION BY NON-STORMWATER DISCHARGES. WHERE ALLOWED NON-STORMWATER DISCHARGES EXIST, THEY MUST BE IDENTIFIED AND STEPS SHOULD BE TAKEN TO ENSURE THE IMPLEMENTATION OF APPROPRIATE POLLUTION PREVENTION MEASURES FOR THE NON-STORMWATER COMPONENT(S) OF THE DISCHARGE. AUTHORIZED NON-STORMWATER DISCHARGES ARE:
- A. DISCHARGES FROM FIREFIGHTING ACTIVITY;
- B. FIRE HYDRANT FLUSHINGS; C. VEHICLE WASHWATER IF DETERGENTS ARE NOT USED AND WASHING IS LIMITED TO THE EXTERIOR OF VEHICLES (ENGINE,
- UNDERCARRIAGE AND TRANSMISSION WASHING IS PROHIBITED); D. DUST CONTROL RUNOFF IN ACCORDANCE WITH PERMIT CONDITIONS
- E. ROUTINE EXTERNAL BUILDING WASHDOWN, NOT INCLUDING SURFACE PAINT REMOVAL, THAT DOES NOT INVOLVE
- F. PAVEMENT WASHWATER (WHERE SPILLS/LEAKS OF TOXIC OR HAZARDOUS MATERIALS HAVE NOT OCCURRED, UNLESS
- ALL SPILLED MATERIAL HAD BEEN REMOVED) IF DETERGENTS ARE NOT USED;
- G. UNCONTAMINATED AIR CONDITIONING OR COMPRESSOR CONDENSATE;
- **UNCONTAMINATED GROUNDWATER OR SPRING WATER;**
- FOUNDATION OR FOOTER DRAIN-WATER WHERE FLOWS ARE NOT CONTAMINATED; UNCONTAMINATED EXCAVATION DEWATERING
- K. POTABLE WATER SOURCES INCLUDING WATERLINE FLUSHINGS; AND
- L. LANDSCAPE IRRIGATION.
- 25. UNAUTHORIZED NON-STORMWATER DISCHARGES: THE MAINEDEP'S APPROVAL UNDER THIS CHAPTER DOES NOT AUTHORIZE A DISCHARGE THAT IS MIXED WITH A SOURCE OF NON\_STORMWATER, OTHER THAN THOSE DISCHARGES IN COMPLIANCE WITH APPENDIX C (6). SPECIFICALLY, THE DEPARTMENT'S APPROVAL DOES NOT AUTHORIZE DISCHARGES OF THE FOLLOWING:
- A. WASTEWATER FROM THE WASHOUT OR CLEANOUT OF CONCRETE, STUCCO, PAINT, FORM RELEASE OILS, CURING COMPOUNDS OR OTHER CONSTRUCTION MATERIALS;
- FUELS, OILS OR OTHER POLLUTANTS USED IN VEHICLE AND EQUIPMENT OPERATION AND MAINTENANCE; C. SOAPS, SOLVENTS, OR DETERGENTS USED IN VEHICLE AND EQUIPMENT WASHING; AND
- TOXIC OR HAZARDOUS SUBSTANCES FROM A SPILL OR OTHER RELEASE.

### **EROSION CONTROL - WINTER CONSTRUCTION**

- 1. WINTER CONSTRUCTION PERIOD DEFINED: NOVEMBER 1 THROUGH APRIL 15.
- 2. CONTINUATION OF EARTHWORK OPERATIONS ON ADDITIONAL AREAS SHALL NOT BEGIN UNTIL THE EXPOSED SOIL SURFACE ON THE AREA BEING WORKED HAS BEEN STABILIZED SUCH THAT NO LARGER AREA OF THE SITE IS WITHOUT EROSION CONTROL PROTECTION AS LISTED IN ITEM 2 ABOVE.
- 3. AN AREA SHALL BE CONSIDERED TO HAVE BEEN STABILIZED WHEN EXPOSED SURFACES HAVE BEEN EITHER MULCHED WITH STRAW AT A RATE OF 100 LB. PER 1,000 SQUARE FEET (WITH OR WITHOUT SEEDING) OR DORMANT SEEDED, MULCHED AND ADEQUATELY ANCHORED BY AN APPROVED ANCHORING TECHNIQUE. IN ALL CASES, MULCH SHALL BE APPLIED SUCH THAT SOIL SURFACE IS NOT VISIBLE THROUGH THE MULCH.
- BETWEEN THE DATES OF OCTOBER 15 AND APRIL 1ST, LOAM OR SEED WILL NOT BE REQUIRED. DURING PERIODS OF ABOVE-FREEZING TEMPERATURES, THE SLOPES SHALL BE FINE GRADED AND EITHER PROTECTED WITH MULCH OR TEMPORARILY SEEDED AND MULCHED UNTIL SUCH TIME AS THE FINAL TREATMENT CAN BE APPLIED. IF THE DATE IS AFTER NOVEMBER 1ST AND IF THE EXPOSED AREA HAS BEEN LOAMED, FINAL GRADED AND IS SMOOTH, THEN THE AREA MUST BE STABILIZED WITH MULCH. IF CONSTRUCTION CONTINUES DURING FREEZING WEATHER, ALL EXPOSED AREAS SHALL BE GRADED BEFORE FREEZING AND THE SURFACE TEMPORARILY PROTECTED FROM EROSION BY THE APPLICATION OF MULCH. SLOPES SHALL NOT BE LEFT EXPOSED OVER THE WINTER OR ANY OTHER EXTENDED TIME OF WORK SUSPENSION UNLESS TREATED IN THE ABOVE MANNER. UNTIL SUCH TIME AS WEATHER CONDITIONS ALLOW DITCHES TO BE FINISHED WITH THE PERMANENT SURFACE TREATMENT, EROSION SHALL BE CONTROLLED BY THE INSTALLATION OF BALES OF HAY OR STONE CHECK DAMS IN ACCORDANCE WITH THE STANDARD DETAILS.
- 5. THE APPLICATION OF MULCH TO FINE GRADED AREAS WILL BE STABILIZED AS FOLLOWS:
- A. BETWEEN THE DATES OF NOVEMBER 1ST AND APRIL 15TH ALL MULCH SHALL BE ANCHORED BY EITHER PEG LINE, MULCH NETTING, ASPHALT EMULSION, CHEMICAL TACK OR WOOD CELLULOSE FIBER.
- B. MULCH NETTING SHALL BE USED TO ANCHOR MULCH IN ALL DRAINAGE WAYS WITH A SLOPE GREATER THAN 3% FOR SLOPES EXPOSED TO DIRECT WINDS AND FOR ALL OTHER SLOPES GRATER THAN 8%. THIS SHALL BE IN ADDITION TO **EROSION CONTROL MATTING-DITCHES DETAIL.**
- C. MULCH NETTING SHALL BE USED TO ANCHOR MULCH IN ALL AREAS WITH SLOPES GREATER THAN 15%. AFTER OCTOBER 1ST, THE SAME APPLIES FOR ALL SLOPES GREATER THAN 8%.
- 8. AFTER NOVEMBER 1ST THE CONTRACTOR SHALL APPLY MULCH AND ANCHORING ON ALL BARE EARTH AT THE END OF EACH WORKING DAY.
- 9. DURING WINTER CONSTRUCTION PERIODS ALL SNOW SHALL BE REMOVED FROM AREAS OF MULCHING PRIOR TO PLACEMENT.
- 10. THE INSPECTION FREQUENCY FOR WINTER CONSTRUCTION SHALL BE AFTER EACH RAINFALL, SNOWSTORM, OR THAWING, AND AT LEAST ONCE A WEEK.


#### **EROSION CONTROL - WETLAND NOTES**

- 1. WETLANDS AND SURFACE WATERS (EXCEPTING THOSE WHICH ARE TO BE FILLED IN ACCORDANCE WITH STATE AND FEDERAL REGULATIONS) WILL BE PROTECTED WITH SILT FENCE INSTALLED AT THE EDGE OF THE WETLAND OR THE BOUNDARY OF WETLAND DISTURBANCE.
- 2. IF THE WORK INCLUDES CROSSING OF WETLANDS AND/OR STREAMS, THE CONTRACTOR SHALL TAKE SPECIAL PRECAUTIONS **WORKING IN THESE AREAS.**
- 3. ANY WETLAND CROSSING WORK SHALL BE COMPLETED BETWEEN THE PERIOD OF MAY 1 AND SEPTEMBER 30.
- 4. ALL EROSION CONTROL MEASURES SHALL BE IN PLACE PRIOR TO COMMENCING CONSTRUCTION WITHIN OR ADJACENT TO WETLAND AREAS. ALL TEMPORARY MEASURES SHALL NOT BE REMOVED UNTIL SITE IS FULLY STABILIZED.
- 5. WETLAND VEGETATIVE LAYERS SHALL BE REMOVED AND SALVAGED FOR RESTORATION OF THE DISTURBED AREAS.
- 6. STORAGE AREAS FOR WETLAND MATERIALS SHALL BE PROPERLY PROTECTED AGAINST EROSION.
- 7. SEEDING OF THE DISTURBED AREAS WITHIN WETLAND AREAS SHALL UTILIZE MIXTURES APPROPRIATE FOR WETLAND AREAS AS OUTLINED IN THE SPECIFICATIONS.

#### INSPECTIONS


REGULAR INSPECTIONS OF ALL EROSION AND SEDIMENTATION CONTROLS SHALL BE MADE AT LEAST WEEKLY AND PRIOR TO AND FOLLOWING STORM EVENTS. MINIMUM INSPECTIONS SHALL BE MADE AS LISTED IN THE TABLE BELOW. SEE INSPECTIONS, MAINTENANCE AND HOUSEKEEPING PLAN FOR ADDITIONAL INFORMATION.


INSPECTED ITEM	EXAMPLE REPAIR INDICATORS
MULCHED SURFACES	THIN MULCH OR INADEQUATE APPLICATION. WIND MOVEMENT
SEEDED SURFACES	POOR SEED GERMINATION. LOSS OF MULCH. DEVELOPMENT OF RIVULETS.
SEDIMENT BARRIER	SEDIMENT BUILD-UP TO ONE HALF THE HEIGHT OF THE BARRIER. UNDERMINING OF THE BARRIER. SUPPORTING STAKES LOOSE, TOPPLED OR UNMARKED. BREAKS IN BARRIER.
PERIMETER DIVERSION	DISCHARGE IS TO STABILIZED AREA. EROSION OR BREAKS IN BARRIER. SUPPORTING STAKES LOOSE, TOPPLED OR UNMARKED.
CATCH BASIN PROTECTION	SEDIMENT BUILD-UP AND STRUCTURE BLOCKAGES. SLOW FLOW/PONDING WATER. BREAKS IN FABRIC OR VOIDS IN BARRIER.
DEWATERING FILTER	BREAKS IN FABRIC OR SUPPORTING STRUCTURE. SLOW FLOW, INDICATING HIGH SEDIMENT BUILD-UP.
CONSTRUCTION ENTRANCE	SEDIMENTATION OF ROADWAYS. OFF-SITE DUST COMPLAINTS.



1. PROVIDE FOR ALL DRAINAGE SWALES. ADDITIONAL REQUIREMENTS MAY APPLY. SEE EROSION CONTROL - WINTER CONSTRUCTION NOTE 7.

# **EROSION CONTROL MATTING - DITCHES**





### SILT FENCE INSTALLATION DETAIL

WOOD WASTE/BARK

THE FOLLOWING STANDARDS:

**WEIGHT BASIS.** 

85% PASSING A 0.75" SCREEN.

**CB INLET GRATE** 

**CURLEX 1 MATTING BY** 

OR APPROVED EQUAL

AMERICAN EXCELSIOR CO.

**RUNOFF** 

1. EROSION CONTROL MIX SHOULD CONTAIN A WELL-GRADED MIXTURE OF PARTICLE SIZES

GROWTH SUCH AS FLY ASH OR YARD SCRAPING. LARGE PORTIONS OF SILTS, CLAYS OR

FINE SANDS ARE NOT ACCEPTABLE IN THE MIX. THE MIX COMPOSITION SHOULD MEET

A. THE ORGANIC MATTER CONTENT SHOULD BE BETWEEN 80% AND 100%, DRY

B. PARTICLE SIZE BY WEIGHT SHOULD BE 100% PASSING A 6" SCREEN AND 70% TO

BE FREE OF REFUSE, PHYSICAL CONTAMINANTS, AND MATERIAL TOXIC TO PLANT

C. THE ORGANIC PORTION NEEDS TO BE FIBROUS AND ELONGATED.

**EROSION CONTROL MULCH BERM** 

EMBED HAYBALES MINIMUM OF 4".

HAY BALE CB INLET PROTECTION

**INSTALL ON SLOPES 3:1 OR GREATER** 

**EROSION CONTROL MATTING - SLOPES** 

D. SOLUBLE SALTS CONTENT SHALL BE < 4.0 MMHOS/CM.

E. THE PH SHOULD BE BETWEEN 5.0 AND 8.0.

2. DO NOT USE ECM BERM AT BASE OF SLOPES 8% OR GREATER.

AND MAY CONTAIN ROCKS LESS THAN 4" IN DIAMETER. EROSION CONTROL MIX SHOULD

**EXISTING GROUND** 

**STAKE HAY BALES** 

**ANCHOR PER** 

OVERLAP EDGES MIN OF 4 INCHES


STAPLE PER MANUFACTURER

**REQUIREMENTS** 

**MANUFACTURER** 


**REQUIREMENTS** 

**AS PER DETAIL** 




EROSION CHECK TO BE BALES OF HAY SECURED TO THE GROUND WITH TWO 4 LONG GRADE STAKES FOR EACH BALE. SAND BAG AS REQUIRED, PLACE SUFFICIENT BALES TO ESTABLISH ELEVATIONS AT(A) AT LEAST 6 INCHES ABOVE OVERFLOW AT(B)


### HAY BALE CHECK DAM



### JOINING SILT FENCE SECTIONS



### **COMBINATION SILT FENCE AND HAY BALE BARRIER**



(TEMPORARY, TO BE REMOVED PRIOR TO FINAL SITE PAVING)

STABILIZED CONSTRUCTION ENTRANCE

**DRAWING** 

**C-8** 

FILTER FABRIC

